Physical Address: No. 01 Seller Street I Nqanqarhu I 5480
Postal Address: P.O. Box 1 I Nqanqarhu I 5480
Tel: **Nqanqarhu**:045 932 8100 I **Ugie:** 045 933 8000 I **Tlokoeng**:039 257 2200
Social Media I Facebook: @Elundini Local Municipality I **X:** @ ElundiniLM
YouTube Channel: @Elundini Local Municipality I **Instagram**: @elundini_lm

Dear Sir/Madam

REQUEST FOR FORMAL WRITTEN PRICE QUOTATIONS

Kindly furnish us with a written quotation for **Repair and renovations of Tlokoeng taxi rank** as detailed in the enclosed list.

The quotation must be submitted on the letterhead of your business in a sealed envelope indicating the name of bid must be deposited in the tender box situated in 1 Seller Street Nqanqarhu, Finance Department, Cashier Reception area before 12h00 on the **07 December 2026.** For **queries,** please email to scm@elundini.gov.za or faxed to 086 216 8784

For Technical Queries: Mr Z. Mabandla **Tel: 045 932 8230**

For Supply Chain Queries: Ms Y. Mpetha **Tel: 045 932 8134**

REPAIRS AND RENOVATIONS OF TLOKOENG TAXI RANK - ELM-3/022/2026-2027

Only those tenderers who satisfy the following eligibility criteria and who provide the required evidence in their tender submission are eligible to submit tenders and have their tenders evaluated:

1. **Tender offers will only be accepted if:**
   1) the tenderer is registered on the Central Supplier Database (CSD) for the South African government (see https://secure.csd.gov.za /) unless it is a foreign supplier with no local registered entity.
   2) the tenderer provides written proof from SARS that the tenderer either has no Tax obligations or has made arrangements to meet outstanding Tax obligations,
   3) the tenderer or any of its directors/shareholders is not listed on the Register of Tender Defaulters in the financial offer is market related (See Regulation 6 (9) and section 7 (9) of the 8(9) OF Preferential Procurement Regulation 2022.
   4) the tenderer or any of its directors/shareholders is not listed on the Register of Tender Defaulters in terms of the Prevention and Combating of Corrupt Activities Act of 2004 as a person prohibited from doing business with the public sector terms of the Prevention and Combating of Corrupt Activities Act of 2004 as a person prohibited from doing business with the public sector.
   5) the tenderer has not:
      i) abused the Employer's Supply Chain Management System; or
      ii) failed to perform on any previous contract and has been given a written notice to this effect; and
      iii) the tenderer has completed the Compulsory Declaration and there are no conflicts of interest which may impact on the tenderer's ability to perform the contract in the best interests of the employer or potentially compromise the tender process.
   6) the statement of municipal account that is not older than three months or Lease Agreement OR Affidavit from SAPS stating that the bidder is not obliged to pay municipal rates with a letter from a ward councillor is submitted with the tender document.
   7) the price(s) quoted are valid for at least ninety (90) days from date of your offer.
   8) the price(s) quoted are firm and are inclusive of VAT where applicable.

9) the Joint Venture has attached the following:
   a) J V agreement,
   b) original or certified copy of consolidated BBBEE certificate, and
   c) letter of signatory.

2. The tenderer is required to submit with his tender the following certificates:

1) Proof of registration with Central Supplier Database must be attached.
2) A Copy of business entity registration certificate e.g. CK Document
3) Certified ID copy/s of business entity owners
4) Latest municipal account statement or lease agreement or affidavit from the South African Police Services and a letter from ward councillor.
5) Tax Compliance status documents with PIN from SARS must be attached
6) CIDB – 1GB or higher

3. Returnable schedules required for tender evaluation processes

MBD 1: Invitation to bid
MBD 4: Declaration of Interest form
MBD 6.1 Preferencial Procurement Policy framework in terms of PPPR 2022 Regulation
MBD 7.1 Purchase of goods and services
MBD 8: Declaration of Bidder's Past Supply Chain Management Practices
MBD 9: Certificate of Independent Bid Determination
Elundini Municipality Supplier Declaration form (which is downloadable on the municipal website)
www.elundini.gov.za

NB: No quotations will be considered from persons in the service of the state

BIDDERS SHOULD TAKE NOTE OF THE FOLLOWING BID CONDITIONS:

1) The Elundini Local Municipality Supply Chain Management Policy will apply;
2) The Elundini Local Municipality does not bind itself to accept the lowest bid or any other bid and reserves the right to accept the whole or part of the bid;
3) Bids which are late, incomplete, unsigned, faxed or sent electronically will not be accepted;
4) Bids submitted are to hold good for a period of 90 days;
5) Bidders will be required to register as a supplier/service provider on the ELM's Supplier/Service Provider Database, if not already registered.
6) The latest General Conditions of Contract and any Special Conditions of Contract will apply.
7) Failure to comply with these conditions may invalidate your offer.
8) Upon submission of a bid/quote the bidder automatically grants confirmation that SARS may, on ongoing basis during the contract term the bidder's tax compliance status to the municipality.
9) General Conditions of Contract 2010 will apply in this Request for Quotation
10) By mere submission of the bid, the bidder automatically consents to deliver within 14 days of issue of an order unless a declaration for variance in this regard has been submitted to the municipality on the day of issue of an order.
11) National Treasury circular no. 9 of 2017/18 Price shall apply.
12) Bidders must be allowed to submit bids by hand or by courier on condition that the responsibility of depositing the tender, bid or proposal lies squarely with the bidder not the Municipality

13) Local Municipalitys Supply Chain Management Policy and the 80/20 preferencial procurement points system for acquisition of goods and services with Rand value equal to or below R50 million will be applied.
14) No services or goods may be rendered/ supplied until an official purchase order has been issued
15) Contract shall be automatically cancelled where conflict of interest was not disclosed

SIGNATURE_____ DATE_____

1. SPECIFICATION

Scope of works, alterations on

- Excavation, Filling, ETC Other Than Bulk
- Concrete, Formwork and Reinforcements
- Masonry
- Waterproofing
- Roof Covering
- Ceiling, Partitions and Access Flooring
- Ironmongery
- Metalwork
- Plaster
- Tilling
- Plumbing and Drainage
- Paintwork
- External Works

Stage 1 of Evaluation: Eligibility Criteria

Only bidders who satisfy the following eligibility criteria and who have provided the required evidence in their tender submission are eligible to have their bid offers evaluated:

1. **Valid proof of standing with compensation for occupational injuries and diseases (COID)**
2. **Valid CIDB: grade 1GB or higher**

Bidders with non-compliant with the above Eligibility Criteria will be disqualified and not be considered for further evaluation

Stage 2 of Evaluation: Functionality

The quality criteria and maximum score in respect of each of the criteria are as follows:

	Evaluation Criteria	Description	Maximum number of points
1.	**1. Past experience**	The contractor must demonstrate the past experience and 2 appointment	2 Project and 2 References letters = 30 points 1 project with 1 reference letter= 15

		letters accompanied and 2 reference letters of the same project	**Total= 30 Points**
2.	**2. Technical Team: Forman**	1. National Diploma in Building 2. CV with past experience of not less than 5 years	1. National Diploma = 15 2. CV with experience not less than 5 years = 15 **Total = 30 Points**
3.	**3. Project life cycle**	Gant chart stipulating 3 months project life cycle to complete the project	Gant Chart with 3 months construction period =**10 points** **Total= 10 Points**
	Total points		70

A maximum score of 70% out of 70 points must be score in order to proceed to price and preferential points

EVALUATION CRITERIA

The 80/ 20 preferential procurement point system for acquisition of goods or services with Rand value equal to or below R50 million will be applied.

Price - **80 points**
Specific Goals - **20 points**

The specific goals allocated points in terms of this tender	**Number of points claimed (80/20 system) (To be completed by the organ of state)**	**Number of points claimed (80/20 system) (To be completed by the tenderer)**	**Proof to claim points**
Tender Price	**80**		
EME or QSE which is at least 51% owned by black people	05 Points		• Company Registration document • Certified B- BBEE certificate or Sworn Affidavit
EME or QSE which is at least 51% owned by Local business within: Elundini Local Municipality= 15 Points Within Joe Gqabi District = 10 Points Outside region = 05 Points	15 Points		• Proof of business residence operation within Elundini Municipality Jurisdiction or outside Elundini Local Municipality within Joe Gqabi District or outside region along with CSD report
Sub-Total (Specific Goals)	**20 Points**		

Bidder that fail to submit proof of specific goal as stipulated above will not be allocated points.

DELIVERY ADDRESS:

Elundini Local Municipality
No.1 Seller Street,
Nqanqarhu
5480

Published on the 23 November 2026

ANNEXURE A: BOQ

Pricing Schedule (Where applicable) NB. Please indicate frequently used items.

[redacted] [redacted]

TENDERED BOQ

	Description	Uom	Quantity	Rate	Amount
	GENERAL NOTES				
	Tenderers are advised to visit the site before tendering and satisfy themselves as to the nature and extent of the works, means of access to the site and availability of working space. No claims will be entertained due to the tenderer having failed to comply with the above tenderer having failed to comply with this conditions.	Notes			
	The descriptions in the items are given as a guide and to assist Contractors in tendering, but are not necessarily accurate or complete. Contractors must verify the items by personal inspection on the site.	Notes			
	Procedure of work;				
	The Project Manager reserves the right to direct the order in which the contract will be executed, should circumstances necessitate such action.	Notes			
	Loss by theft, fire or otherwise;				

The risk of loss by theft, fire, storm, riot or otherwise of the materials therein shall rest entirely with the Contractor immediately upon the handing over of the site. S/he shall take steps as s/he may deem fit for his own protection against such loss.	Notes		
SECTION A : PRELIMINARIES			
Facilities for the Contractor:			
Storage shed F:..... V:..... T:.....	Item	1,00	
Office shed F:..... V:..... T:.....	Item	1,00	
Living accommodation F:..... V:..... T:.....	Item	1,00	
Ablution and equipment F:..... V:..... T:.....	Item	1,00	
Site progress meetings once a month F:..... V:..... T:....	Months	5,00	
Water supplier, electric power and communication F:..... V:..... T:.....	Item	1,00	
Removal of site Establishment F:..... V:..... T:.....	Item	1,00	
Management of works	Item	1,00	

	F:..... V:..... T:.....				
	Site instructions must be in writing in an adequate triplicate carbon site book of A4 size which must be kept in the office on site and provided by the Contractor. F:..... V:..... T:.....	Item	1,00		
	LABOUR RATES				
	The tenderer is informed that the labour rate for local unskilled laboure during the construction period will be a minimum of R230.00 per day. F:..... V:..... T:.....	Item	1,00		
	h) The tenderer is inforced that the CLO must be provided by Muncipality and his or her allowance is provided with the provissional sum at a rate of R6 000.00 per month. F:..... V:..... T: 100%	Months	1,00		
	Allow for attendence and profit on the above .....%	Item	1,00		
	CARRIED FORWARD BROUGHT FORWARD				
	Two Security/watchman or day and night shift at a rate of R250 Per day for day shift and R300 per day for night shift F:..... V:..... T:.....	Months	1,00		

	Temporal main notice board to be approved by municipal's representative	Item	1,00		
	Occupatinal Health & Safety				
	Occupational Health and Safety File F:..... V:..... T:.....	Item	1,00		
	Set of PPE for employees made of 100% cotton 2 piece work suite, helmet, safety boots, hand gloves and dust maks as when required, etc. F:..... V:..... T:.....	No	1,00		
	Occupational Health and Safety Rep for the duration of the contract F:..... V:..... T:.....	Item	1,00		
	Allow profit and attendence on the above .....%	Item	1,00		
	SETTING OUT OF THE WORKS				
	Setting out of the entire works F:..... V:..... T:.....	Item	1,00		
	Temporal access to site				
	Allow for temporal access to site by preparing the surface for better access. F:..... V:..... T:.....	Item	1,00		
	Project Staring Committee Site Meetings Allowance at R350,00 per seating once a month for 8 members F:..... V:..... T:.....	Months	1,00		
	Allow for profit and attendence on the above .....%	Item	1,00		

	Works insurance for the duration including for liabilty period F:..... V:..... T:.....	Item	1,00		
	Allow R5000. 00/pm for a student training in built environment to be provided by the client for tye duration of the project F:..... V:..... T:.....	Item	1,00		
	Allow for profit and attendence on the above .....%	Item	1,00		
	CARRIED TO FINAL SUMMARY				**R -**

[redacted] [redacted]

SECTION B

BILL NO. 1

ALTERATIONS

For Preambles see "PW371 - A Edition 2,1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014).

REMOVAL OF EXISTING WORK

Taking out and removing doors, windows, ironmongery, etc from brickwork thresholds, sills, etc including building up openings and making good finishes (making good paintwork elsewhere measured)					
Timber single door and door frames not exceeding 2,5m2	No	1,00		R	-
Timber double door and door frames not exceeding 5m2	No	2,00		R	-
Mortice lock set	No	2,00		R	-
Taking out and removing piping, sanitary fittings, etc., including cutting off as necessary, disconnecting piping from fittings and making good floor and wall finishes (making good tiling and paintwork elsewhere)					

[redacted]

	Vitreous china wash hand basin	No	4,00		R	-
	Vitreous china WC pan with cistern, including short lengths of piping, etc.	No	6,00		R	-
	PVC gutters including brackets, etc	m	0,00		R	-
	Taking out/off and removing glass and mirrors					
	Glass from steel windows, including cleaning out rebates and preparing for new glass	m2	0,00		R	-
	Taking down and removing roofs, floors, panelling, ceilings, partitions, etc.					
	Gypsum plasterboard ceilings, including cornices, timber brandering, etc.	m²	5,00		R	-
	Taking out and removing sundry joinery work, fittings, etc.					
	Timber skirtings	m	0,00		R	-
	Taking out/off and removing sundry metalwork					
	Burglar gates, set aside for re-use including making good plaster finish	No	2,00		R	-
	CARRIED TO COLLECTION				R	-

[redacted] [redacted]

	BILL NO.1 : FOUNDATIONS				
	EXCAVATION, FILLING, ETC OTHER THAN BULK				
	Excavation in earth not exceeding 2m deep:				
	Trenches.	m^3	65,00		
	Column bases.	m^3	2,00		
	Extra over trench and hole excavations in earth for excavation in:				
	Soft rock.	m^3	4,00		
	Hard rock.	m^3	1,00		
	Extra over all excavations for carting away:				
	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m^3	37,00		
	Risk of collapse of excavations:				
	Sides of trench and hole excavations not exceeding 1,5m deep.	m^2	185,00		
	Keeping excavations free of water:				
	Keeping excavations free of all water other than subterranean water.	Item	1,00		

[redacted]

	Earth filling obtained from the excavations and/or prescribed stock piles on site :				
	Backfilling to trenches, holes, etc.	m^3	28,00		
	Approved sabunga earth filling supplied by the Contractor compacted to 98%:				
	Under floors, steps, pavings, etc.	m^3	210,00		
	SOIL POISONING				
	Approved brand of anti-termite soil poison applied by a Registered Pest Control company and guaranteed against termite infestation for ten years:				
	Under floors, etc., including forming and poisoning shallow furrows against foundation walls, etc., filling in furrows and ramming.	m^2	310,00		
	CARRIED TO COLLECTION				

[redacted] [redacted]

	BILL NO.2 : CONCRETE, FORMWORK AND REINFORCEMENT				
	REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES				
	25Mpa/19mm Concrete in:				
	Strip footings.	m^3	21,00		
	25Mpa/19mm Concrete in:				
	Surface beds on waterproofing.	m^3	34,00		
	Steps, ramps etc	m^3	4,00		
	Bases.	m^3	1,00		
	Making and testing set of three 150 x 150 x 150mm concrete strength test cubes (Provisional).	Sets	3,00		
	FINISHING TOP SURFACE OF CONCRETE				
	Finishing top surfaces of concrete smooth with a wood float:				
	Surface beds, slabs, etc.	m^2	310,00		
	Stairs, ramps, etc	m^2	15,00		

[redacted]

	MOVEMENT JOINTS ETC				
	Saw cut joints:				
	3 x50mm Saw cut joints in top of concrete.	m	34,00		
	Vertical joggle construction joints through concrete including thick cement slurry to one face:				
	Surface beds not exceeding 300mmm thick.	m	15,00		
	CARRIED FORWARD				

[redacted] [redacted]

	BROUGHT FORWARD				
	ROUGH FORMWORK (DEGREE OF ACCURACY II) (CPAP Work Group No 111)				
	Steps.	m²	12,00		
	Risers.	m	28,00		
	REINFORCEMENT (PROVISIONAL) (CPAP Work Group No 114)				
	REF. 193 fabric reinforcement in concrete surface beds, slabs, etc.	m²	310,00		
	High Tensile Reinforecement in Footing cut, bent, delivered on site and fixed to position;				
	10mm	t	0,20		
	12mm	t	0,66		
	CARRIED TO COLLECTION				

[redacted]

BILL NO.3 : MASONRY
BRICKWORK

Sizes in descriptions:
Where sizes in descriptions are given in brick units, 'one brick' shall represent the length and 'half brick' the width of a brick.

BRICKWORK IN FOUNDATIONS (PROVISIONAL)

Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar:

One brick walls in foundations.	m²	124,00		
Brickwork forming 330x220mm columns	m³	3,00		

BRICKWORK IN SUPERSTRUCTURE

Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar:

Brickwork forming 330x220mm columns	m³	5,00		
Half brick wall in beamfilling170mm high.	m²	5,00		
Half brick wall.	m²	1,00		
One brick wall	m²	393,00		

BRICKWORK SUNDRIES

	2mm thick fully galvanised high tensile brickwork reinforcement:				
	75mm Wide reinforcement built in horizontally.	m	20,00		
	115mm Wide reinforcement built in horizontally.	m	2300,00		
	Prestressed prefabricated lintels:				
	110 x 75mm Lintels in lengths not exceeding 3m.	m	11,00		
	Turning pieces				
	220mm Wide turning piece to lintels,etc	m	28,00		
	CARRIED FORWARD				

[redacted]

BROUGHT FORWARD				R	-
FACE BRICKWORK					
Allow the prime cost amount of R6500.00 net per thousand bricks for FBX face brick-on-edge header course, coping, sills etc. supplied and delivered to site and add for taking delivery, storage, building in and pointing with recessed horizontal and vertical joints, waste and profit:					
Extra over brickwork for face brickwork;					
In foundation	m^2	28,00			
In brick pier	m^2	6,00			
In superstructure	m^2	337,00			
FACE BRICKWORK COPING, SILLS ETC.					
220mm Wide cut sill set sloping and slightly projecting	m	22,00			
Face brick on edge lintel course in cement mortar 220mm wide with soffit and pointing on 110mm projection soffit and one side	m	28,00			
Facebrick cleaning					

	Continuous wash down using a fibre brush, scrub down the brickwork from top to bottom and then rinse with clean water to remove excess mortar and scrab to remove all loose material, mortar etc	m²	0,00		R	-
	FIBRE CEMENT WINDOW SILLS:					
	Everite Nutec' fibre cement window sills in single lengths not exceeding 3.6m bedded in class 1 cement mortar including fixing lugs screwed to underside withself tapping screws :					
	15 x 150mm Wide sills set flat and slightly projecting.	m	22,00			
	CARIED TO COLLECTION				**R**	-

	BILL NO.4 : WATERPROOFING				
	DAMPPROOFING OF WALLS AND FLOORS				
	One layer of 375 micron Consol Plastics Brikgrip DPC embossed damp proof course:				
	In walls.	m²	25,00		
	One layer of 250 micron Consol Plastics Gunplas USB Green waterproof sheeting sealed at laps with Gunplas Pressure Sensitive Tape:				
	Under surface beds.	m²	310,00		
	Vertically between fill and brickwork.	m²	8,00		
	Two coats of brixeal waterproofing bitumen emulsion paint				
	On the outer surface of the inner skin of 230mm thick brick wall in stages, during constructionn.	m²	337,00		
	Clear silicone sealant				
	In joint sealing and pointing between external window or timber door frames and facebrick surround.	m	135,00		
	CARRIED TO COLLECTION				

[redacted] [redacted]

	BILL NO.5 : ROOF COVERINGS					
	CORRUGATED METAL SHEETING AND ACCESSORIES (CPAP Work Group No 124)					
	Inspection of roof leaks					
	Inspect the roof leaks and use an equally approved sealant	m²	5,00		R	-
	CARRIED TO COLLECTION				**R**	-

[redacted]

	BILL NO.6 : CARPENTRY AND JOINERY **EAVES, VERGES, ETC** **Everite PVC' barge boards:**					
	80 x 200mm Socketless barge board , joined with PVC H profile joiners and screwed to sprocket ends.	m	10,00		R	-
	Everite FC77 pressed fibre-cement:					
	15 x 225mm Fascias including galvanised steel H-profile jointing strips fixed to rafterfeet.	m	10,00		R	-
	SKIRTINGS **Wrought meranti:**					
	19 x75mm Skirting plugged.	m	10,00		R	-
	CARRIED TO COLLECTION				**R**	-
	FRAMED DOORS ETC					
	Wrought meranti doors: 44x90mm Wrought meranti framed framing.	m	0,00		R	-
	Wrought meranti doors hung to steel frames					
	F-L HARDWOOD SOLID FLUSH PANEL DOOR					
	813 x 2032 x 40mm F & L stable hardwood solid door with hardwood solid door with hardwood finish for suitable painting.	no	1,00		R	-

	1520 x 2032 x 40mm F & L stable hardwood solid door with hardwood solid door with hardwood finish for suitable painting.	no	2,00		R	-
	F-L hardwood solid flush panel door size 1620 x 2100	No.	0,00		R	-
	CARRIED TO COLLECTION				**R**	-

	BILL NO.7 : CEILINGS PARTITIONS AND ACCESS FLOORING					
	NAILED UP AND SCREW UP CEILINGS (CPAP Work Group No 126)					
	6.4mm "Rhino" gypsum plasterboard Sloping ceilings including 38 x 38mm sawn softwood brandering at 450mm centres fitted with PVC "H" strips	m²	5,00		R	-
	Extra over ceiling for 600 x 600mm trap door of 38 x 50mm wrought softwood rebated framing with one 38 x 5mm sawn softwood cross brander covered with ceiling board and fitted flush in opening.	No.	0,00		R	-
	DECORATIVE MOULDINGS AND CORNICES (CPAP Work Group No 126)					
	Rhino' Moulded Gypsum Cornices:					
	75mm Coved cornice.	m	10,00		R	-
	CARRIED TO COLLECTION				**R**	**-**

	BILL NO. 8 : IRONMONGERY **IRONMONGERY**					
	SUPPLEMENTARY PREAMBLES **Finishes to ironmongery:** **HINGES, FLOOR SPRING HINGES, BOLTS, PANIC BOLTS, ETC**					
	Solid:					
	110mm Brass hinge with nylon washers.	No.	6,00		R	-
	150mm Brass barrel bolt with keep let into concrete.	No.	2,00		R	-
	150mm Chromium plated brass barrel bolt.	No.	2,00		R	-
	CATCHES, CABIN HOOKS, ETC					
	LOCKS					
	Solid:					
	Three lever rebated lockset.	No.	2,00		R	-
	LETTERS, NAMEPLATES, ETC.					
	150 x 150mm anodised PVC plat signage.	No.	0,00		R	-
	SUNDRIES					
	32 mm Diameter black rubber door stop plugged to concrete floor.	No.	0,00		R	-

[redacted] [redacted]

	Stainless steel cabin hook mounted to wall and door	no	0,00		R	-
	CARRIED TO COLLECTION				**R**	-

[redacted]

	BILL NO.9 : METALWORK **WELDED GALVANISED SCREENS, GATES, ETC.**					
	Steel door baglar guards to 800x 1000mm window openings made of x R12mm round bars with vertical steel members welded top and bottom at 150mm c/c with three horizontal bars horizontal steel bars at 250mm c/c welded on vertical bars.	No				
	Fully Galvanised steel gate size 1350 x 2000m high for doubke doors made up of of 30 x30 x 1,6mm thick hollow section frame filled in with 2 intermediate horizontal 30 x 25 members with R12mm round bars vertical steel rails welded on a pair of suitable hinges welded to post and hasp and staple	No				
	STEEL FRAME WINDOWS					
	Fully galvanised frame for window 1022 x 1559 mm high type TD575	No	22,00			
	CARRIED TO COLLECTION				**R**	-

[redacted] [redacted]

	BILL NO.10 : PLASTERING					
	INTERNAL PLASTER					
	Cement plaster on brickwork:					
	On narrow widths.	m²	8,00		R	-
	CARRIED TO COLLECTION				**R**	**-**

[redacted]

	BILL NO.11 : TILING					
	CERAMIC FLOOR TILING					
	Prepare surface and apply adhesive cemet motar and lay approximates 600 x 600 x 6mm thick porcelain floor tiles including an approved grouting colour on tiles and cleaning of the finished work					
	On floors	m²	310,00			
	On stairs and ramps	m²	18,00			
	Sundries					
	Alluminium edging strip;					
	On extl coners/angles	m	45,00			
	CARRIED COLLECTION				**R**	-

[redacted] [redacted]

BILL NO.12 : PLUMBING AND DRAINAGE						
RAINWATER DISPOSAL						
SUPASPAN Type 285 Aluminium gutters and fixing in strict accordance with the manufacturer's instructions						
125 x 80mm Ogee eaves gutter including fixing to falls on patent brackets spaced at maximum 1000mm centres fixed to fibre reinforced cement fascia with brass bolts with nuts and washers.	m	61,29		R	-
Extra over 100mm eaves gutter for stopped end.	No.	4,00		R	-
Extra over100mm eaves gutter for outlet for 75mm pipe.	No.	6,00		R	-
75mm Rainwater pipes fixed to walls to empty into rainwater tanks including angles etc.	m	4,00		R	-
Extra over down pipes for bend	no	4,00		R	-
Ditto but shoe	no	4,00		R	-
SANITARY FITTINGS					
510 x 405mm 'Hibiscus' 'Avocado' colour vitreous	No	4,00		R	-
Vaal Sanitaryware' vitreous china WC suites:					

[redacted]

	WC 'white vitreous china floor mounted (product code 7502) comprising 90° outlet pan (product code 7502) and matching 9 litre cistern (product code 710539)	No	4,00		R	-
	Servicing fittings, etc:					
	Check, adjust and service 15mm pillartap including	No	4,00		R	-
	Check, adjust and service 15mm bibtap including	No	4,00		R	-
	SANITARY PLUMBING					
	uPVC pipes:					
	50mm Pipes.	m	5,00		R	-
	110mm Pipes.	m	10,00		R	-
	Extra over uPVC pipes for fittings:					
	50mm BSP adaptor.	No	4,00		R	-
	50mm Access bend.	No	4,00		R	-
	110mm GI Two-way vent valve.	No	4,00		R	-
	TESTING:					
	Testing waste pipe system.	Item	1,00		R	-
	FIRE APPLIANCES ETC.					
	Chubb':					

[redacted]

	9 Litre foam fire extinguisher.	No.	3,00		R	-
	CARRIED TO COLLECTION				**R**	**-**

[redacted]

	BILL NO.13 : PAINTWORK					
	ON FLOATED PLASTER					
	Prepare and apply one coat plaster primer thinned 20% with mineral turpentine and two coats Plascon Double Velvet enamel paint					
	On interior walls.	m²	205,00		R	-
	ON PLASTER BOARD					
	Prepare and apply one coat sealer/undercoat and two coats Plascon Polvin Super Acrylic PVA paint					
	On ceilings and cornices.	m²	5,00		R	-
	On fascia and bargeboard.	m²	61,29		R	-
	On fiber cement internal window sills	m²	15,00		R	-
	ON METAL					
	Spot priming bare metal surfaces with zinc phosphate metal primer, one coat universal undercoat and two coats super universal enamel paint on work in sound condition on steel					
	On internal burglar gates.	m²	12,96		R	-
	ON WOOD, WOOD BOARD					

[redacted] [redacted]

	Stop, sand down and prepare wood surfaces and apply three coats 'Plascon Woodcare' high gloss clear varnish:					
	On interior doors.	m²	19,44		R	-
	On interior door frames.	m²	4,00		R	-
	On interior skirtings, rails, etc not exceeding 300 mm girth.	m	10,00		R	-
	CARRIED TO COLLECTION				**R**	**-**

[redacted]

	Bill No 14; EXTERNAL WORKS				
	EXTERNAL WORK (Provisional)				
	Facebrick cleaning				
	Continuos wash down using a fibre brush, scrub down the brickwork from top to bottom and then rinse with clean water to remove excess mortar and scrab to remove all loose material, moter etc	m²	0,00	R	-
	CARRIED TO COLLETION			**R**	**-**

[redacted] [redacted]

SECTION B

COMMUNITY HALL COLLECTION

Bill No. 1 : Alterations	R	-
Bill No. 1 : Foundation	R	-
Bill No. 2 : Conc, Formwork, Reinforcement	R	-
Bill No. 3 : Masonry	R	-
Bill No. 4 : Waterproofing	R	-
Bill No. 5 : Roof Covering	R	-
Bill No. 6 : Carpentry & Joinery		
Bill No. 7 : Ceiling Partition & Access Flooring	R	-
Bill No. 8 : Iron Mongery	R	-
Bill No. 9 : Metal Works	R	-
Bill No. 10 : Plastering	R	-
Bill No. 11 : Tiling	R	-
Bill No. 12 : Plumbing & Drainage	R	-
Bill No. : 13 : Paint Works	R	-

[redacted]

[redacted]

Bill No. 14 : External Works **CARRIED TO SUMMARY**			**R -** **R -**

[redacted] [redacted]

SECTION C **BILL NO.18 : PROVISIONAL SUMS**					
Electrical installation:					
Provide the amount of R5,000.00 (Five Thousand Rands) only for Electrical repairs and Rehabilitation	Item	1,00		R	-
Profit on above item.....%	Item	1,00		R	-
Attendance on ditto.....%	Item	1,00		R	-
Water Connection					
Provide the amount of R8 000.00 (Eight Thousand Rand) for water connection to the Municipal Line.	Item	1,00		R	-
Profit on above item.....%	item	1,00		R	-
Attendance on ditto.....%	item	1,00		R	-
CARRIED TO SUMMARY				**R**	-
FINAL SUMMARY					
Prelimenaries & Generals				**R**	-
Community Hall				**R**	-
Provisional Sum				**R**	-
SUB TOTAL				**R**	-
ADD VAT @ 15%				**R**	-
TOTAL SUM CARRIED TO FORM OF OFFER				**R**	-